

Turntide Building App for Daikin VRV: Set-Up Process and Responsibility Chart



This document walks through the steps involved (and who's responsible) to set up the Turntide Building App with a Daikin VRV system.

#	Step	Details	Turntide	Rep (Channel Partner)	Subcontractors	IT Department	Building Operator
1	Project Definition (Scope, Equipment Schedules & Submittals, SOO's)	Rep (Channel Partner) has an opportunity, and sends relevant information to Turntide for a quote		✓			✓
2	Proposal and TT Submittal	Turntide sends a quote back to the Rep (Channel Partner) with project details in a submittal package	✓				
3	Job Acceptance & PO	Rep (Channel Partner) accepts the quote, and submits a purchase order (PO) to Turntide		✓			
4	Product Assembly & Delivery	Turntide assembles the project kit, and delivers to the shipping address from the purchase order	✓				
5	Install Product HW at Site	Rep (Channel Partner) and subcontractors install kit at customer location		✓	✓		
6	Network Connection	Rep (Channel Partner) and/or subcontractors verify network connectivity with Turntide once installation is complete, and system is powered up Get IP information from the IT department to set up the IP address on the Hub		✓		✓	
7	Equipment Addressing	Rep (Channel Partner) provides equipment schedule, field addressing, and setting details for all equipment to be integrated		✓	✓		
8	Sequence Logic & Control Points	Rep (Channel Partner) completes Turntide Sequence of Operations selection form to specify logic programming options		✓	✓		
9	Turntide System Engineering	The Turntide Automation Services Team remotely programs and configures the kit exactly to customer specifications. Configuration steps include configuring the Turntide Hub, equipment, alarms, notifications, schedules, equipment graphics, floorplan graphics, IAQ dashboard, logic, reporting, Proportional Energy Reporting (PER), and BACnet server (depending on the scope of work as defined by the Rep). Turntide will then verify completion and commission the system	✓				
	Configure Hub		✓				
	Equipment Configuration		✓				
	Alarms		✓				
	Notification Configuration		✓				
	Schedule Configuration		✓				
	Equipment Graphics		✓				
	Floorplan Graphics		✓				
	IAQ Dashboard		✓				
	Logic		✓				
	Report		✓				
	PER Report		✓				
	BACnet Server		✓				
	Verify Completion		✓				
Commissioning	✓						
10	Schedule Training & Add User Accounts	Rep (Channel Partner) schedules hand-off training for buildings operations team, and provides a list of authorized users, with assigned permissions		✓			
11	Provide Owner Training	Turntide delivers remote operator training	✓				✓
12	Close Out	Project installation is deemed complete and the site is transitioned to live operations status	✓	✓	✓	✓	✓